





Up on closer investigation around the damage areas, it was found that the cedar shingles were installed with electro galvanized roofing nails that were not compatible with the shingles. The majority of the nail heads had rusted off and the surrounding shingles were loose and could be easily lifted off of the roof with very little effort. Thus, the scope of the repair work was expanded by face nailing every one of the shingles on the roof.

