

X-\MD\2016\20165029\CAD\Site\dwa\00\C 100 Existing Conditions Plan

- 2. REFER TO SHEET C100 FOR BENCHMARKS, DATUM, AND TOPOGRAPHIC ELEMENTS.
- 3. CONTRACTOR SHALL VERIFY LOCATION OF WORK AND REPORT ANY DISCREPANCIES TO THE ENGINEER PRIOR TO COMMENCING

## **REMOVAL NOTES**

- CONTRACTOR SHALL VERIFY ALL EXISTING UTILITY LINES NOTED FOR ABANDONMENT OR REMOVAL. EXISTING UTILITIES THAT ARE TO BE ABANDONED OR REMOVED SHALL BE RESPECTIVELY ABANDONED OR REMOVED TO THE LOCATIONS INDICATED ON THIS PLAN. ALL UTILITY STRUCTURES LOCATED ALONG REMOVED UTILITY LINES SHALL BE REMOVED IN THEIR ENTIRETY.
- 2. ASPHALT AND CONCRETE PAVEMENT NOTED FOR REMOVAL SHALL BE SAW CUT TO FULL DEPTH PRIOR TO REMOVAL.
- 3. CONCRETE CURB AND GUTTER AND SIDEWALK NOTED FOR REMOVAL SHALL BE REMOVED AT THE NEAREST JOINT.
- 4. ITEMS SCHEDULED FOR REMOVAL AND EXCESS EXCAVATED MATERIALS SHALL BE DISPOSED OF OFF-SITE IN ACCORDANCE WITH ANY APPLICABLE REGULATIONS.
- 5. CONTRACTOR IS RESPONSIBLE FOR SECURING THE JOB SITE TO PROTECT THE PUBLIC.
- 6. CONTRACTOR IS RESPONSIBLE FOR COMPLIANCE WITH LOCAL ORDINANCES FOR DUST CONTROL.
- 7. UTILITIES SHALL BE REMOVED TO LOCATIONS INDICATED ON PLANS.
- 8. CONTRACTOR SHALL COMPLY WITH LOCAL, STATE, AND FEDERAL CODES, RULES AND REGULATIONS APPLICABLE TO DEMOLITION WORK INCLUDING BUT NOT LIMITED TO EROSION CONTROL, AIR POLLUTION, NOISE POLLUTION, AND WASTE DISPOSAL.
- 9. CONTRACTOR SHALL REPLACE PAVEMENT, CURB AND GUTTER, TREES, LAWN AREA, ANY ABOVE GROUND APPETENCIES, OR ANY OTHER ITEM THAT WAS DAMAGED AS A RESULT OF CONSTRUCTION RELATED ACTIVITIES AS DEEMED BY OWNERS REPRESENTATIVE THAT WAS NOT CALLED OUT FOR REMOVAL OR REPLACEMENT. CONTRACTOR SHALL REPLACE/REPAIR DAMAGED ITEM TO THE SATISFACTION OF OWNER'S REPRESENTATIVE AT NO ADDITIONAL COST TO THE OWNER.
- 10. TREE PROTECTION FENCING LOCATIONS SHOWN ARE APPROXIMATE. ALL EXISTING TREES OUTSIDE OF PROJECT LIMITS ARE INTENDED TO REMAIN. FINAL LOCATIONS OF FENCING SHALL BE DETERMINED IN THE FIELD AND AS IDENTIFIED ON CONSTRUCTION DETAILS. ADDITIONAL FENCING MAY BE REQUIRED. COORDINATE WITH OWNER'S REPRESENTATIVE. TREE PROTECTION FENCE SHALL REMAIN IN PLACE THROUGHOUT CONSTRUCTION.
- 11. REMOVE ALL PLANTER POTS AND TRASH CANS. COORDINATE WITH THE CITY OF MADISON ON FINAL LOCATION.
- 12. CONTRACTOR SHALL FILL ALL EXISTING VAULTS SURROUNDING THE BUILDING THAT ARE TO BE ABANDONED.

In accordance with Wisconsin statute 182.0175, damage to

drawing, and further, excavator shall comply with all other

requirements of this statute relative to excavator's work.

ransmission facilities, excavator shall be solely responsible to

provide advance notice to the designated "ONE CALL SYSTEM"

not less than three working days prior to commencement of any excavation required to perform work contained on this

The underground utilities shown have been located from field


no quarantees that the underground utilities shown comprise Il such utilities in the area, either in service or abandoned. The surveyor further does not warrant that the underground

survey information and existing drawings. The surveyor makes

tilities shown are in the exact location indicated although he

does certify that they are located as accurately as possible rom information available. The surveyor has not physically

ocated the underground utilities.



## **EROSION CONTROL NOTES**

**LEGEND** 

- 1. CONSTRUCTION SITE EROSION CONTROL AND SEDIMENTATION CONTROL SHALL COMPLY WITH THE REQUIREMENTS OF THE CITY OF MADISON, AND SHALL EMPLOY EROSION CONTROL METHODS AS SHOWN AND SPECIFIED IN THE WISCONSIN DEPARTMENT OF NATURAL RESOURCES (WDNR) "CONSTRUCTION SITE EROSION AND SEDIMENT CONTROL TECHNICAL STANDARDS".
- 2. ALL EROSION CONTROL MEASURES SHALL BE ADJUSTED TO MEET FIELD CONDITIONS AT THE TIME OF CONSTRUCTION AND SHALL BE INSTALLED PRIOR TO ANY GRADING OR DISTURBANCE OF EXISTING SURFACE MATERIAL ON THE SITE.

AND REINSTALL TREE GRATE.

- 3. ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE CHECKED FOR STABILITY AND OPERATION AFTER A RAINFALL OF 0.5 INCHES OR MORE, BUT NO LESS THAN ONCE EVERY WEEK. MAINTENANCE OF ALL EROSION CONTROL STRUCTURES SHALL BE PROVIDED TO INSURE INTENDED PURPOSE IS ACCOMPLISHED. REPAIRS AND MAINTENANCE SHALL BE COMPLETED WITHIN 24 HOURS OF INSPECTION. CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANUP AND REMOVAL OF ALL SEDIMENT WHEN LEAVING PROPERTY. EROSION CONTROL MEASURES MUST BE IN WORKING CONDITION AT END OF EACH WORK DAY.
- 4. PERIODIC STREET SWEEPING SHALL BE COMPLETED TO MAINTAIN THE PUBLIC STREET FREE OF DUST AND
- 5. CONSTRUCTION SEQUENCE FOR EROSION CONTROL INCLUDES:
  - INSTALL INLET PROTECTION. REMOVE EXISTING PAVEMENT AND UTILITIES NOTED FOR REMOVAL
- PERFORM MASS EXCAVATION
- COMPLETE BUILDING CONSTRUCTION, INSTALLING ALL OTHER UTILITIES, AND FINAL GRADING. PAVE PARKING LOTS, DRIVES, AND SIDEWALKS.
- 6. REMOVE EROSION CONTOL DEVICES ONCE THE SITE IS STABILIZED AND PERMANENT VEGETAION IS ESTABLISHED AS APPROVED BY THE ENGINEER.

6. SITE DEWATERING. WATER PUMPED FROM THE SITE SHALL BE TREATED BY APPROPRIATE BEST MANAGEMENT PRACTICES SPECIFIED IN THE WDNR "CONSTRUCTION SITE EROSION AND SEDIMENT CONTROL TECHNICAL STANDARDS" AND IN ACCORDANCE WITH CITY OF MADISON ENGINEERING DEPARTMENT. WATER SHALL NOT BE DISCHARGED IN A MANNER THAT CAUSES EROSION OF THE SITE, ADJACENT SITES, OR RECEIVING CHANNELS.

-CAP EXISTING SANITARY

SEWER LATERAL

- 7. WASTE AND MATERIAL DISPOSAL. ALL WASTE AND UNUSED BUILDING MATERIALS (INCLUDING GARBAGE, DEBRIS, CLEANING WASTES, WASTEWATER, TOXIC MATERIALS, OR HAZARDOUS MATERIALS) SHALL BE PROPERLY DISPOSED AND NOT ALLOWED TO BE CARRIED OFF-SITE BY RUNOFF OR WIND.
- 8. SEDIMENT CLEANUP. ALL OFF-SITE SEDIMENT DEPOSITS OCCURRING AS A RESULT OF A STORM EVENT SHALL BE CLEANED UP BY THE END OF THE NEXT WORK DAY. ALL OTHER OFF-SITE SEDIMENT DEPOSITS OCCURRING AS A RESULT OF CONSTRUCTION ACTIVITIES SHALL BE CLEANED UP BY THE END OF THE THE WORK DAY.
- 9. WHEN THE DISTURBED AREA HAS BEEN STABILIZED BY PERMANENT VEGETATION OR OTHER MEANS, TEMPORARY BEST MANAGEMENT PRACTICES.
- 10. NOTIFY THE CITY OF MADISON WITHIN TWO WORKING DAYS OF COMMENCING ANY LAND DEVELOPMENT OR LAND DISTURBING ACTIVITY.
- 11. NOTIFY THE CITY OF MADISON OF COMPLETION OF ANY BEST MANAGEMENT PRACTICES WITHIN THE NEXT WORKING DAY AFTER THEIR INSTALLATION.
- 12. OBTAIN PERMISSION IN WRITING FROM THE CITY OF MADISON ENGINEERING DEPARTMENT PRIOR TO MODIFYING THE EROSION CONTROL PLAN. NOTIFY WDNR AT LEAST FIVE WORKING DAYS PRIOR TO IMPLEMENTING CHANGES TO THE EROSION CONTROL PLAN.
- 13. REPAIR ANY SILTATION OR EROSION DAMAGE TO ADJOINING SURFACES AND DRAINAGE WAYS RESULTING FROM LAND DEVELOPMENT OR LAND DISTURBING ACTIVITIES.
- 14. KEEP A COPY OF THE EROSION CONTROL PLAN ON SITE.

REMAIN AND BE PROTECTED

DURING CONSTRUCTION

122 STATE ST.

NEW HOTEL AND RESTAURANT

122 STATE ST. MADISON, WI. 53703

KKAD METROSTUDIO

SCALE: 1" = 20"

STRUCTURAL/CIVIL ENGINEER: GRAEF 5126 W. TERRACE DRIVE MADISON, WI 53718 P. 604.242.1550

MEP ENGINEER: 46 RIVERSIDE AVE. WESTPORT, CT 06880 P. 203.299.0250


LANDUSE APPLICATION 07.12.18 REVISION / ISSUE DATE

THESE DOCUMENTS HAVE BEEN PREPARED BY ME OR UNDER MY CLOSE PERSONAL SUPERVISION, AND THEY COMPLY WITH ALL CITY REQUIREMENTS

SHEET TITLE:

DEMOLITION AND EROSION CONTROL PLAN

PROJECT #: #PIn



NOTICE: In accordance with Wisconsin statute 182.0175, damage to transmission facilities, excavator shall be solely responsible to provide advance notice to the designated "ONE CALL SYSTEM" not less than three working days prior to commencement of any excavation required to perform work contained on this drawing, and further, excavator shall comply with all other requirements of this statute relative to excavator's work.

DISCLAIMER:
The underground utilities shown have been located from field survey information and existing drawings. The surveyor makes no guarantees that the underground utilities shown comprise all such utilities in the area, either in service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated although he does certify that they are located as accurately as possible from information available. The surveyor has not physically

ocated the underground utilities.

122 STATE ST.

NEW HOTEL AND RESTAURANT

122 STATE ST. MADISON, WI. 53703

KKAD METROSTUDIO

CONSULTANTS:

STRUCTURAL/CIVIL ENGINEER:

MADISON, WI 53718

P. 604.242.1550

P. 203.299.0250

5126 W. TERRACE DRIVE

MEP ENGINEER:
CDA
46 RIVERSIDE AVE.
WESTPORT, CT 06880

1 LANDUSE APPLICATION 07.12.18
# REVISION / ISSUE DATE

SEA


THESE DOCUMENTS HAVE BEEN PREPARED BY ME OR UNDER MY CLOSE PERSONAL SUPERVISION, AND THEY COMPLY WITH ALL CITY REQUIREMENTS


SHEET TITLE:


OVERALL SITE PLAN

PROJECT #: #PIn


C300








X:\MD\2016\20165029\CAD\Site\dwq\00\C\_400\_Site\_Grading\_Plan\_5029



X:\\\\D\2016\20165029\CAD\Site\dwg\00\C\_500\_Site\_Utility\_Plan\_5029



X:\MD\2016\20165029\CAD\Site\dwg\00\C\_600\_Fire\_Access\_Plan\_5029