## **PROJECT SUMMARY AND FACT SHEET:**



Darwin Road Resurfa	cing with Utilities Assessment Di	strict - 2019 Madison	
Project Engineer:	Steve Sonntag 267-1997		
Alder:	Larry Palm, Dist 12		
Project Limits:	Darwin Road from Packers Avenue to International Lane		
Project Summary:	The proposed project is a Utility Replacement with Resurfaicing Project. The pavement will be replaced within the project limits. Sanitary sewer will be replaced. Storm sewer Inlets and structures will be adjusted as needed. Curb and gutter will be replaced as needed to repair any damaged sections and as required for the installation of sanitary sewer laterals. The right of way is 66 feet wide. Darwin Road is 40 feet wide with no geometric changes proposed.		
Street: Darwin Road	Existing	Proposed	
Project Type Last Surfaced Pavement Rating Curb Rating Width	1986 3 7 40 ft face to face	Resurfacing Asphalt Pavement 40 ft face to face	
Surface Type	Asphalt Pavement	Asphalt Pavement	
		Province d	
Storm Sewer Work Required Design Storm Size Material Year	Existing Varies: 12 - 24 Inches RCP 1986	Proposed structure adjustments, as needed	
Sanitary Sewer	Existing	Proposed	
Work Required		Replace main and laterals	
Size	8 inches	8 Inches	
Material	VP	PVC	
Year	1953	2019	
Water Main	Existing	Proposed	
Work Required		None Proposed	
Size	10 inches		
Material	spun cast iron		
Year	1942		
Parking	Existing	Proposed	
Parking Conditions	Parking Allowed with Restrictions	No Proposed Changes	_
Street Lighting	Existing	Proposed	
Street Lighting	Wood Poles	No Proposed Changes	
Cost	<b>\$0.40.000.00</b>		
Total Cost	\$840,000.00		
Street Assessments Sanitary Assessments	\$30,000.00		
City of Madison Cost	\$810,000.00		
Assessment Policy	The east of evicting concrete items (	9 gutter eidewelk and drive aprenet is seesed 500/ to see the	
	owners with remaining 50% paid by the The cost for sanitary laterals is assessed	<ul> <li>&amp; gutter, sidewalk and drive aprons) is assessed 50% to property</li> <li>City. New sidewalk is assessed 100% to property owners.</li> <li>25% to property owner with remaining 75% paid by City.</li> <li>as are assessed 100% to the property owner requiring the connection</li> </ul>	on.

Costs for private storm sewer connections are assessed 100% to the property owner requiring the connection. Assessments are payable in one lump sum or over a period of 8 years, with 3.0% interest charged on unpaid balance.

## Schedule

Start Date	June 2019	
Project Duration	Approximately 2 Months	
Traffic Calming:	None	
Traffic Detours:	ffic Detours: No posted detours are planned	
Real Estate Requirements:	None	
Tree Information: Forestry will trim as needed no tree removal proposed at this ti		

Rain Garden Information:

Project does not qualify for rain gardens.

## **Project Location:**

