DAYTON/CARROLL CORNER PERSPECTIVE







CARROLL STREET PERSPECTIVE







STATE STREET WEST-FACING PERSPECTIVE







STATE STREET EAST-FACING PERSPECTIVE








DAYTON STREET PERSPECTIVE





























RESULTANT BUILDING VOLUME

PROPOSED NEW BUILDING






VIEW FROM BASCOM HILL LOOKING EAST TOWARD SITE





VIEW FROM LANGDON &CARROLL LOOKING SOUTHEAST TOWARD SITE





VIEW FROM STATE & JOHNSON LOOKING EAST TOWARD SITE






VIEW FROM WEST WASHINGTON & CARROLL LOOKING NORTHWEST TOWARD SITE







TORAL PARCEL AREA	9,835 S.F.	0.23 ACRES
RIGHT - OF - WAY PAVED AREA	4,995 S.F.	0.11 ACRES
RIGHT - OF - WAY LANDSCAPED AREA	0 S.F.	0.00 ACRES
TOTAL SITE AREA	14,830 S.F.	0.34 ACRES

BASEMENT	13,125 S.F
FIRST FLOOR/ LOBBY	13,125 S.F
2ND FLOOR	12,989 S.F
3RD FLOOR	12,989 S.F
4TH FLOOR	12.579 S.F
5TH FLOOR	10,131 S.F
6TH FLOOR	10,131 S.F
7TH FLOOR	10,131 S.F
8TH FLOOR	10,131 S.F
BAR/ LOUNGE/ TERRACE	10,057 S.F
ROOF/ MECH	5,216 S.F
GROSS BUILDING	106,388 S.F
OVERALL BUILDING SITE	13,237 S.F
LOT COVERAGE	99%
USABLE OPEN SPACE	0 S.F
LANDSCAPE AREA	0 S.F.
PAVED AREA	0 S.F.
TOTAL ROOM NUMBER	133

UNIT SIZE BREAKDOWN BY BEADROOM = SEE ARCHITECTURAL PLANS NUMBER AND SIZE OF TENANT UNIT = SEE ARCHITECTURAL PLANS

122 STATE ST.

NEW HOTEL AND RESTAURANT

122 STATE ST. MADISON, WI. 53703

X KKAD METROSTUDIO

1 ISSUED FOR PLANNING 06/20/18 # REVISION / ISSUE DATE


SHEET TITLE:

ARCHITECTURAL SITE PLAN

PROJECT #. #Pin

A-2.1

























X:\MD\2016\20165029\CAD\Site\dwg\00\C_100_Existing_Conditions_Pk 7/12/2018 4:55 PM

- REFER TO SHEET C100 FOR BENCHMARKS, DATUM, AND TOPOGRAPHIC ELEMENTS.
- CONTRACTOR SHALL VERIFY LOCATION OF WORK AND REPORT ANY DISCREPANCIES TO THE ENGINEER PRIOR TO COMMENCING WORK.

REMOVAL NOTES

- CONTRACTOR SHALL VERIFY ALL EXISTING UTILITY LINES NOTED FOR ABANDONMENT OR REMOVAL EXISTING UTILITIES THAT ARE TO BE ABANDONED OR REMOVED SHALL BE RESPECTIVELY ABANDONED OR REMOVED TO THE LOCATIONS INDICATED ON THIS PLAN. ALL UTILITY STRUCTURES LOCATED ALONG REMOVED UTILITY LINES SHALL BE REMOVED IN THEIR ENTIRETY.
- ASPHALT AND CONCRETE PAVEMENT NOTED FOR REMOVAL SHALL BE SAW CUT TO FULL DEPTH PRIOR TO REMOVAL.
- CONCRETE CURB AND GUTTER AND SIDEWALK NOTED FOR REMOVAL SHALL BE REMOVED AT THE NEAREST JOINT.
- . ITEMS SCHEDULED FOR REMOVAL AND EXCESS EXCAVATED MATERIALS SHALL BE DISPOSED OF OFF-SITE IN ACCORDANCE WITH ANY APPLICABLE REGULATIONS.
- CONTRACTOR IS RESPONSIBLE FOR SECURING THE JOB SITE TO PROTECT THE PUBLIC.
- CONTRACTOR IS RESPONSIBLE FOR COMPLIANCE WITH LOCAL ORDINANCES FOR DUST CONTROL.
- 7. UTILITIES SHALL BE REMOVED TO LOCATIONS INDICATED ON PLANS.
- 8. CONTRACTOR SHALL COMPLY WITH LOCAL, STATE, AND FEDERAL CODES, RULES AND REGULATIONS APPLICABLE TO DEMOLITION WORK INCLUDING BUT NOT LIMITED TO EROSION CONTROL, AIR POLLUTION, NOISE POLLUTION, AND WASTE DISPOSAL.
- CONTRACTOR SHALL REPLACE PAVEMENT, CURB AND GUTTER, TREES, LAW AREA, ANY ABOVE GROUND APPETENCIES, OR ANY OTHER ITEM THAT WAS DAMAGED AS A RESULT OF CONSTRUCTION RELATED ACTIVITIES AS DEEMED BY OWNERS REPRESENTATIVE THAT WAS NOT CALLED OUT FOR REMOVAL OR REPLACEMENT. CONTRACTOR SHALL REPLACE/REPAIR DAMAGED ITEM TO THE SATISFACTION OF OWNER'S REPRESENTATIVE AT NO ADDITIONAL COST TO THE OWNER.
- 10. TREE PROTECTION FENCING LOCATIONS SHOWN ARE APPROXIMATE.
 ALL EXISTING TIRES OUTSIDE OF PROJECT LIMITS ARE INTENDED
 TO REMAIN, FINAL LOCATIONS OF FENCING SHALL BE DETERMINED
 IN THE FIELD AND AS IDENTIFIED ON CONSTRUCTION DETAILS.
 ADDITIONAL FENCING MAY BE REQUIRED, COORDINATE WITH OWNER'S REPRESENTATIVE. TREE PROTECTION FENCE SHALL REMAIN IN PLACE THROUGHOUT CONSTRUCTION.
- 11. REMOVE ALL PLANTER POTS AND TRASH CANS. COORDINATE MITH THE CITY OF MADISON ON FINAL LOCATION.
- 12. CONTRACTOR SHALL FILL ALL EXISTING VAULTS SURROUNDING THE BUILDING THAT ARE TO BE ABANDONED.

-ASPHALT PAVEMENT REMOVAL -CONCRETE PAVEMENT REMOVAL X X X X X X X -SAWCUT -CONCRETE CURB AND GUTTER REMOVAL 5~XQ -SITE FEATURE REMOVAL -INLET PROTECTION REMOVE EXISTING RAMP AND TRUNCATED DOMES -TREE PROTECTION ASPHALT PAVEMENT REMOVAL (TYP.) -TREE REMOVAL EXISTING SKYWALK TO BE-REMOVED PEDESTRIAN CROSSING SIGN AND POLE TO BE REMOVED, SALVAGED, AND REINSTALLED PER THE CITY OF MADISON EXISTING STREET LIGHT TO BE REMOVED, SALVAGED, AND REINSTALLED PER THE CITY OF MADISON -REMOVE, SALVAGE, AND REINSTALL STORM INLET CASTING CONCRETE PAVEMENT REMOVAL (TYP.) REMOVE BOLLARDS, PARKING SIGNS, PARKING NUMBERS, AND PARKING PAY STATION. COORDINATE WITH THE CITY OF MADISON ON STORAGE LOCATION PARKING SIGNS AND STREET LIGHTS TO REMAIN -REMOVE EXISTING PARKING STRIPING AND HANDICAP PAINT (TYP.) AND BE PROTECTED -REMOVE, SALVAGE, AND REINSTALL STORM INLET CASTING CAP EXISTING -EXISTING UTILITIES TO REMAIN AND BE PROTECTED (TYP.) REE REMOVAL (TYP.) GUTTER REMOVAL (TYP.) NLET PROTECTION (TYP.) STREET LIGHT TO REMAIN PUBLICEXISTING CURB AND GUTTER LOT 3 SPACE TO REMAIN (TYP.) BLOCK 77 LOT 2 EXISTING PAVEMENT TO REMAIN BLOCK 77 CSM No. 13100 -RELOCATE BIKE RACK AS CAP EXISTING SANITARY. LOT 1 SEWER LATERAL CONSTRUCTION BLOCK 77 -CAP EXISTING LIGHT POLE TO REMAIN AND WATER SERVICE BE PROTECTED (TYP.) STORM LATERAL -SAWCUT (TYP.) - SAN -SAN -— SAN —⊕ STATE STREET __ MTS _____ MTS ___ - STM TREES TO REMAIN AND BE -PROTECTED. REMOVE, SALVAGE, AND REINSTALL TREE GRATE. -EXISTING LIGHT POLES TO REMAIN AND BE PROTECTED DURING CONSTRUCTION (TYP.) -CAP EXISTING SANITARY

EROSION CONTROL NOTES

LEGEND

- 1. CONSTRUCTION SITE EROSION CONTROL AND SEDIMENTATION CONTROL SHALL COMPLY WITH THE REQUIREMENTS OF THE CITY OF MADISON, AND SHALL EMPLOY EROSION CONTROL METHODS AS SHOWN AND SPECIFIED IN THE WISCONSIN DEPARTMENT OF NATURAL RESOURCES (WDNR) "CONSTRUCTION SITE
- ALL EROSION CONTROL MEASURES SHALL BE ADJUSTED TO MEET FIELD CONDITIONS AT THE TIME OF CONSTRUCTION AND SHALL BE INSTALLED PRIOR TO ANY GRADING OR DISTURBANCE OF EXISTING SURFACE MATERIAL ON THE SITE.
- 3. ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE CHECKED FOR STABILITY AND OPERATION AFTER A RAINFALL OF 0.5 INCHES OR MORE, BUT NO LESS THAN ONCE EVERY WEEK. MAINTENANCE OF ALL EROSION CONTROL STRUCTURES SHALL BE PROVIDED TO INSURE INTENDED PURPOSE IS ACCOMPLISHED. REPAIRS AND MAINTENANCE SHALL BE COMPLETED WITHIN 24 HOURS OF INSPECTION. CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANUP AND REMOVAL OF ALL SEDIMENT WHEN LEAVING PROPERTY. EROSION CONTROL MEASURES MUST BE IN WORKING CONDITION AT END OF EACH WORK DAY.
- 4. PERIODIC STREET SWEEPING SHALL BE COMPLETED TO MAINTAIN THE PUBLIC STREET FREE OF DUST AND
- 5. CONSTRUCTION SEQUENCE FOR EROSION CONTROL INCLUDES:
 - INSTALL INLET PROTECTION.
 REMOVE EXISTING PAVEMENT AND UTILITIES NOTED FOR REMOVAL
- REMOVE EXISTING PAVEMENT AND UTILITIES NOTED FOR REMOVAL PERFORM MASS EXCAVATION COMPLETE BUILDING CONSTRUCTION, INSTALLING ALL OTHER UTILITIES, AND FINAL GRADING. PAVE PARKING LOTS, DRIVES, AND SIDEWALKS. REMOVE BROSION CONTOL DEVICES ONCE THE SITE IS STABILIZED AND PERMANENT VEGETAION IS ESTABLISHED AS APPROVED BY THE ENGINEER.

- 6. SITE DEWATERING. WATER PUMPED FROM THE SITE SHALL BE TREATED BY APPROPRIATE BEST MANAGEMENT PRACTICES SPECIFIED IN THE WONR "CONSTRUCTION SITE EROSION AND SEDIMENT CONTROL TECHNICAL STANDARDS" AND IN ACCORDANCE WITH CITY OF MADISON ENGINEERING DEPARTMENT. WATER HALL NOT BE DISCHARGED IN A MANNER THAT CAUSES EROSION OF THE SITE, ADJACENT SITES, OR
- 7. WASTE AND MATERIAL DISPOSAL. ALL WASTE AND UNUSED BUILDING MATERIALS (INCLUDING GARBAGE, DEBRIS, CLEANING WASTES, WASTEWATER, TOXIC MATERIALS, OR HAZARDOUS MATERIALS) SHALL BE PROPERLY DISPOSED AND NOT ALLOWED TO BE CARRIED OFF—SITE BY RUNOFF OR WIND.
- 8. SEDIMENT CLEANUP. ALL OFF-SITE SEDIMENT DEPOSITS OCCURRING AS A RESULT OF A STORM EVENT SHALL BE CLEANED UP BY THE END OF THE NEXT WORK DAY. ALL OTHER OFF-SITE SEDIMENT DEPOSITS OCCURRING AS A RESULT OF CONSTRUCTION ACTIVITIES SHALL BE CLEANED UP BY THE END OF THE THE
- WHEN THE DISTURBED AREA HAS BEEN STABILIZED BY PERMANENT VEGETATION OR OTHER MEANS, TEMPORARY BEST MANAGEMENT PRACTICES.
- 10. NOTIFY THE CITY OF MADISON WITHIN TWO WORKING DAYS OF COMMENCING ANY LAND DEVELOPMENT OR LAND DISTURBING ACTIVITY.
- 11. NOTIFY THE CITY OF MADISON OF COMPLETION OF ANY BEST MANAGEMENT PRACTICES WITHIN THE NEXT WORKING DAY AFTER THEIR INSTALLATION.
- 12. OBTAIN PERMISSION IN WRITING FROM THE CITY OF MADISON ENGINEERING DEPARTMENT PRIOR TO MODIFYING THE EROSION CONTROL PLAN. NOTIFY WORK AT LEAST FIVE WORKING DAYS PRIOR TO IMPLEMENTING CHANGES TO THE EROSION CONTROL PLAN.

13. REPAIR ANY SILTATION OR EROSION DAMAGE TO ADJOINING SURFACES AND DRAINAGE WAYS RESULTING FROM LAND DEVELOPMENT OR LAND DISTURBING ACTIVITIES.

14. KEEP A COPY OF THE EROSION CONTROL PLAN ON SITE.

122 STATE ST.

NEW HOTEL AND RESTAURANT

122 STATE ST. MADISON, WI. 53703

X KKAD METROSTUDIO

5126 W. TERRACE DRIVE MADISON, WI 53718 P. 604.242.1550

> 46 RIVERSIDE AVE. WESTPORT CT 06880 P. 203.299.0250

ANDUSE APPLICATION 07.12.18 DATE


THESE DOCUMENTS HAVE BEEN PREPARED BY ME OR UNDER MY CLOSE PERSONAL SUPERVISION, AND THEY COMPLY WITH ALL CITY REQUIREMENTS


SHEET TITLE


DEMOLITION AND EROSION CONTROL PLAN


6\20 4:55

NOTICE: In accordance with Wisconsin statute 182.0175, damage to transmission facilities, excavator shall be solely responsible to provide advance notice to the designated "ONE CALL SYSTEW" not less than three working days prior to commencement of any excavation required to perform work contained on this drawing, and further, excavator shall comply with all other requirements of this statute relative to excavator's work. DISCLAMER:
The underground utilities shown hove been located from field survey interests that the underground utilities are underground utilities. The surveyor makes are underground utilities shown comprise all such utilities in the underground utilities shown comprise all such utilities in the orea, either in service or obandoned. The surveyor further does not warront that the underground utilities shown are in the exact location indicated atthough he from information available. The surveyor has not physically located the underground utilities.











X:\MD\2016\20165029\CAD\Site\dwg\00\C_400_Site_Grading_Plan_



K:\MD\2016\20165029\CAD\Site\dwg\00\C_500_Site_Utility_Plan_ 743\2018 4-56 BM



X:\MD\2016\20165029\CAD\Site\dwg\00\C_600_Fire_Access_Plan