## Dairy Drive Assessment District - 2019

Project Engineer	Andrew Zwieg ph: 266-9219 email: azwieg@cityofmadison.com	
Project Limits Alder: 16 Tierney	East Broadway to Femrite Drive (see map on reverse)	
	· · · · · ·	<b>_</b>
Street Project Type: New Street Construct	Existing	Proposed
Last Surfaced	NA	NA
Pavement Rating	NA	New Pavement
Curb Rating	NA	New Curb & Gutter
Width	NA	36'
		2' (STA 104+25 - STA 109+50 RT); To
Shoulder	NA	accommodate swale
Surface Type	NA	Asphalt
Sidewalk & Terraces		
Terraces	NA	7.5' Grass
Sidewalks	NA	New 5' Sidewalk (west side of street). Sidewalk not placed on the east side to minimize wetland impacts.
Storm Sewer	Existing	Proposed
Work Required: Install New Storm S		• • • • • • • • • • • • • • • • • • • •
Size	NA	New Pipes
Material	NA	Concrete
Year	NA	2020
Sanitary Sewer	Existing	Proposed
Work Required: Install New Sanitar	/ Sewer	· · ·
Size	NA	New 8" Pipes
Material	NA	PVC
Year	NA	2020
Biofiltration Basin	NA	Located southeast of Dairy Dr, where the street turns north. To used to collect and pre-treat run off from the street before it enters the wetland parcel to the east. The pond will need to achieve 80% TSS reduction.
Water Main	Existing	Proposed
Water Main Work Required: Install New Water M	Existing Asin	Proposed
Size	NA	New 10" Pipes
Material	NA	Ductile Iron
Year	NA	2020
Parking Existing Parking Conditions: NA Proposed Parking: Parking On Both	Sides of the Street.	
		Dranaad
Street Lighting Area Street Lighting	Existing NA	Proposed New Street Lights (City Owned)
Pedestrian Lighting	NA	NA
6 6		
Land Purchases Street right-of-way has been purcha	and	
Trees Existing trees in conflict with the new are developed and driveway entrand Assessment Policy	w street will be removed. There is no propos ces are established.	ed tree plantings planned. Trees will be planted once the lots
Asphalt Pavement/Gravel Base	Owner 100% / City 0%	
Curb & Gutter Sidewalk	Owner 100% / City 0% Owner 100% / City 0%	
Driveway Aprons	Owner 100% / City 0%	
Street Lighting	Owner 100% / City 0%	
Sanitary Sewer	Owner 100% / City 0%	
Water Main	Owner 100% / City 0%	
Water Main Laterals	Owner 100% / City 0%	
Storm Sewer	Owner 100% / City 0%	
Assessments payable in one lump s	sum or over a period of 8 years, with 4% inte	erest charged on unpaid balance.
Schedule		
Advertise for bids	Winter 2020	
Anticipated Construction Start	April 2020	
Approximate Duration	Approx. 4 months	
Costs           Total Cost: \$1,451,343.32           Assessments: \$1,451,343.32           City Cost: \$0.00		
Correspondence		

Correspondence Several In-Person Meetings - Met w/1 of 2 property owners affected by the real estate acquisition. Met w/Alder to discuss new street. see Map on reverse

